

SECTION 01 58 13

TEMPORARY PROJECT SIGNAGE

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Project identification sign.
- B. Project informational signs.

1.02 RELATED REQUIREMENTS

- A. Contract Documents - Uniform General Conditions and Supplemental General Conditions for the State of Texas; and Special Conditions: Requirements for this Section, in addition to requirements herein.

1.03 REFERENCE STANDARDS

- A. FHWA (SHS) - Standard Highway Signs; Federal Highway Administration, U.S. Department of Transportation; 2004.

1.04 QUALITY ASSURANCE

- A. Design sign and structure to withstand 90 miles/hr wind velocity.
- B. Sign Manufacturer to have experience in manufacturing signage with references on similar projects.
- C. Finishes, Vinyl: Adequate to withstand weathering, fading, and chipping for duration of construction.

1.05 SUBMITTALS

- A. See Section 01 30 00 - Administrative Requirements for submittal procedures.
- B. Shop Drawing: Show content, layout, lettering, color, foundation, structure, sizes and grades of members.

PART 2 PRODUCTS

2.02 MANUFACTURERS

- A. Signs:
 - 1. Your Sign Company, LLC. (YSC)
 - 2. Substitutions: See Section 01 60 00

2.02 SIGN MATERIALS

- A. Structure and Framing: New, wood, structurally adequate.
- B. Sign Surfaces: Exterior grade plywood with medium density overlay, minimum 3/4 inch thick, standard large sizes to minimize joints.
- C. Rough Hardware: Galvanized.
- D. Vinyl: Exterior quality; sign background of color as selected.
- E. Lettering: Vinyl or digitally printed, colors as selected.

2.02 PROJECT IDENTIFICATION SIGN

- A. One vinyl graphic sign, 64 sq ft area, bottom 4 feet above ground.
- B. Graphic Design, Colors, Style of Lettering: Designated by Architect.

2.03 PROJECT INFORMATIONAL SIGNS

- A. Vinyl informational signs of same colors and lettering as Project Identification sign, or standard products; size lettering to provide legibility at 100 foot distance.
- B. Provide at field office, and directional signs to direct traffic into and within site. Relocate as Work progress requires.
- C. Provide municipal traffic agency directional traffic signs to and within site.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install project identification sign within 14 days after date fixed by Notice to Proceed.
- B. Erect at designated location.
- C. Erect supports and framing on secure foundation, rigidly braced and framed to resist wind loadings.
- D. Install sign surface plumb and level. Anchor securely.
- E. Exposed surfaces of sign, supports, and framing to be treated lumber.

3.02 MAINTENANCE

- A. Maintain signs and supports clean, repair deterioration and damage.

3.03 REMOVAL

- A. Remove signs, framing, supports, and foundations at completion of Project and restore the area.

END OF SECTION